

Proceedings of the State Environment Impact Assessment Authority Kerala

Present: Prof. (Dr.) K.P. Joy, Chairman, Dr. J. Subhashini. Member. Sri. P.H.Kurian, I.A.S. Member Secretary.

Sub: SEIAA- Environmental Clearance for the construction of new Hospital building for Augmentation of Sree Chitra Thirunal Institute for Medical Science and Technology (SCTIMST), Trivandrum under PMSSY scheme in Survey No.44 & 42/1 Part Block No.6, Cheruvackal Village, Thiruvananthapuram Taluk & Thiruvananthapuram District, Kerala by Dr.Asha Kishore, MD, DM, Director, Sree Chitra Thirunal Institute for Medical Science -Granted - Orders issued.

STATE ENVIRONMENT IMPACT ASSESSMENT AUTHORITY, KERALA

File No. 1164/EC/SEIAA/KL/2017

Dated, Thiruvananthapuram 17/03/2018

- Ref: Application received on 14.11.2017 from Dr.Asha Kishore, Director, Sree Chitra 1. Institute for Medical Science and Technology (SCTIMST), Thiruvananthapuram
 - Minutes of the 83rd meeting of SEAC held on 20th & 21st December 2017. Minutes of the 84th meeting of SEAC held on 22nd & 23rd January 2018

 - Minutes of the 85th SEAC meeting held on 12th February 2018
 - Received from Sree Chitra Tirunal Institute for Medical Science & Technology Letter No.CIVIL/SCTIMST/NHB dt.06.03.2018
 - 6. Minutes of the 81st meeting of SEIAA held on 8th March 2018.
 - Affidavit dated 17th March 2018 from Dr.Asha Kishore, M.D., DM, Chitra Tirunal Institute for Medical Sciences Technology, Thiruvananthapuram

Environmental Clearance No. 54/2018

Dr. Asha Kishore, MD, DM, Director, Sree Chitra Thirunal Institute for Medical College Technology, Medical Campus, Medical Thiruvananthapuram Kerala - 695 011 vide application received on 14.11.2017, has sought Environmental Clearance under EIA Notification, 2006 for the proposed construction of new Hospital building for Augmentation of Sree Chitra Thirunal Institute for Medical Science and Technology (SCTIMST), Trivandrun under PMSSY scheme in Survey No.44 & 42/1 Part Block No.6, Cheruvackal Village, Thiruvananthapuram Taluk & Thiruvananthapuram District, Kerala. It is interalia, noted that the project comes under the Category $B_{\rm s}$ 8(a) of Schedule of EIA Notification 2006.

Details of project as furnished by the applicant are as follows:-

BASIC INFORMATION OF BUILDING PROJECT (To be filled in by the Project Proponent) PART A

File No F.No. :1164/EC/SEIAA/KL/2017 Proposal No.: SIA/KL/NCP/70946/2017 Construction of New Hospital Building for Augmentation of Sree Chitra Thirmal Institute for Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 under PMSSY scheme Dr. Asha Kishore, MD,DM, Director Sree Chitra Thirmal Institute for Medical College PO, Thiruvananthapuram -695 011 under PMSSY scheme Dr. Asha Kishore, MD,DM, Director Sree Chitra Thirmal Institute for Medical Sciences and Technology, Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 Thiruvananthapuram -695 011 Thiruvananthapuram -695 011 Thiruvananthapuram Post of the land Survey Nos. District/Taluk/ and Village etc. Sy.No. 44 & 42/1 Part Block No.6, Cheruvackal Village, Thiruvananthapuram Taluk, Thiruvananthapuram District, Kerala 8 (a) - Building and Construction Projects, Category/B. 14th November 2017 Proposal No.: SIA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors): 3160 Sqm 3. Multi Level Car Parking : 4600 Sqm The height of the building will be 36.75m from Ground Level GPS Co-ordinate The proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirumal Institute for Medical Sciences and	DDU	PART A DECT DETAILS
Proposal No.: SIA/KL/NCP/70946/2017 Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and Technology (SCTIMST), Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 under PMSSY scheme Dr. Asha Kishore, MD,DM, Director Sree Chitra Thirunal Institute for Medical Sciences and Technology, Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 Thiruvananthapuram Taluk, Thiruvananthapuram Taluk, Thiruvananthapuram District, Kerala S (a) - Building and Construction Projects, Category-B. Date of submission of Application Path November 2017 Proposal No. :SIA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors): 3160 Sqm 3. Multi Level Car Parking : 4600 Sqm 3. (Hospital Block, Service Block and Multi Level Car Parking) The height of the building will be 36.75m from Ground Level GPS Co-ordinate Thirunal Institute for Medical Sciences and Thirumal Institute for Medical Sciences and Thirumal Institute for Medical Sciences and Thirumal Institute for Medical Sciences and Thirus Institute for Medical Sciences and Thirus Institute for Medical Sciences and Thirus I	PRO.	
Construction of New Hospital Building for Augmentation of Sree Chitra Thirmal Institute for Medical Sciences and Technology (SCTIMST) Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 under PMSSY scheme Dr. Asha Kishore, MD,DM, Director Sree Chitra Thirmal Institute for Medical Sciences and Technology, Medical College Campus, Medical College Compus, Medical College PO, Thiruvananthapuram -695 011 Thiruvananthapuram -695 011 Thiruvananthapuram District, Kerala Sy. No. 44 & 42/1 Part Block No.6, Cheruvackal Village, Thiruvananthapuram Taluk, Thiruvananthapuram District, Kerala Signy-B. 14 st November 2017 Proposal No. SIA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors): 3160 Sqm 3. Multi Level Car Parking 1 Geometry 1 Ground Level Car Parking 1 Ground Level Latitude (N): 8°31°16.00° N Longitude(E): 76°55'37.00° B The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and	File No	
Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and Technology (SCTIMST), Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 under PMSSY scheme Dr. Asha Kishore, MD,DM, Director Sree Chitra Thirunal Institute for Medical Sciences and Technology, Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 Thiruvananthapuram District, SCTIMST Owner of the land Survey Nos. District/Taluk/ and Village etc. Category/Sub Category and Schedule Category/Sub Category and Schedule Date of submission of Application Total Built up Area & No. of Floors Owner of the land Area & No. of Floors Total Built up Area & No. of Floors The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors): 3160 Sqm 3. (Hospital Block, Service Block and Multi Level Car Parking) The height of the building will be 36.75m from Ground Level Latitude (N): 8°31°16.00° N Longitude(E): 76°55°37.00° E The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and		
Sree Chitra Thirunal Institute for Medical Sciences and Technology, Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 Thiruvananthapuram. Dr. Asha Kishore, MD,DM, Director, SCTIMST Owner of the land Survey Nos. District/Taluk/ and Village etc. Category/Sub Category and Schedule Date of submission of Application Date of submission of Application Total Built up Area & No. of Floors Thiruvananthapuram District, Kerala 8 (a) - Building and Construction Projects, Category-B. 14 ^{lu} November 2017 Proposal No. :SIA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors): 3160 Sqm 3. (Hospital Block, Service Block and Multi Level Car Parking) The height of the building from the ground level GPS Co-ordinate Brief description of the project. Thirumal Institute for Medical Sciences and	Name /Title of the project	Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and Technology (SCTIMST), Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 under PMSSY
Survey Nos. District/Taluk/ and Village etc. Survey Nos. District/Taluk/ and Village etc. Category/Sub Category and Schedule Date of submission of Application Date of submission of Application Total Built up Area & No. of Floors The proposal No. :SIA/KL/NCP/70946/2017 The propos	Name and address of project proponent.	Sree Chitra Thirunal Institute for Medical Sciences and Technology, Medical College Campus, Medical College PO, Thiruvananthapuram -695 011 Thiruvananthapuram.
Survey Nos. District/Taluk/ and Village etc. Sy.No. 44 & 42/1 Part Block No.6, Cheruvackal Village, Thiruvananthapuram Taluk, Thiruvananthapuram District, Kerala 8 (a) - Building and Construction Projects, Category-B. 14 ^{tu} November 2017 Proposal No. :SLA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors):3160 Sqm 3. Multi Level Car Parking: 4600 Sqm No of apartments Height of the building from the ground level GPS Co-ordinate GPS Co-ordinate Sy.No. 44 & 42/1 Part Block No.6, Cheruvackal Village, Thiruvananthapuram Taluk, Thiruvananthapuram District, Kerala 8 (a) - Building and Construction Projects, Category-B. 14 ^{tu} November 2017 Proposal No. :SLA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (G+4 Floors):3160 Sqm 3. Multi Level Car Parking: 4600 Sqm The height of the building will be 36.75m from Ground Level Latitude (N): 8°31'16.00" N Longitude(E): 76°55'37.00" E The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and		Dr. Asha Kishore, MD,DM, Director, SCTIMST
Cheruvackal Village, Thiruvananthapuram Taluk, Thiruvananthapuram District, Kerala 8 (a) - Building and Construction Projects, Category-B. 14 th November 2017 Proposal No. :SIA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors):3160 Sqm 3. Multi Level Car Parking : 4600 Sqm 3. Hospital Block, Service Block and Multi Level Car Parking) Height of the building from the ground level GPS Co-ordinate Brief description of the project. Cheruvackal Village, Thiruvananthapuram Taluk, Thiruvananthapuram District, Kerala 8 (a) - Building and Construction Projects, Category-B. 14 th November 2017 Proposal No. :SIA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors): 3160 Sqm 3. Multi Level Car Parking : 4600 Sqm The height of the building will be 36.75m from Ground Level Car Parking) The height of the building will be 36.75m from Ground Level Latitude (N): 8°31°16.00° N Longitude(E): 76°55'37.00° E The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and	Owner of the land	
Category/Sub Category and Schedule Date of submission of Application Date of submission of Application 14 th November 2017 Proposal No. :SIA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors):3160 Sqm 3. Multi Level Car Parking: 4600 Sqm 3. (Hospital Block, Service Block and Multi Level Car Parking) Height of the building from the ground level GPS Co-ordinate Car Parking: Latitude (N): 8°31'16.00" N Longitude(E): 76°55'37.00" E The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and		Cheruvackal Village, Thiruvananthapuram Taluk,
Date of submission of Application 14 th November 2017 Proposal No.: SIA/KL/NCP/70946/2017 The proposed Built-up area of new hospital block will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors):3160 Sqm 3. Multi Level Car Parking: 4600 Sqm 3. Multi Level Car Parking: 4600 Sqm 4. Graving The height of the building from the ground level GPS Co-ordinate The height of the building will be 36.75m from Ground Level Latitude (N): 8°31'16.00" N Longitude(E): 76°55'37.00" E The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and	Category/Sub Category and Schedule	8 (a) - Building and Construction Projects,
will be 28,478 Sqm. It will be constructed as 3 blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors):3160 Sqm 3. Multi Level Car Parking: 4600 Sqm 3. (Hospital Block, Service Block and Multi Level Car Parking) Height of the building from the ground level GPS Co-ordinate The height of the building will be 36.75m from Ground Level Latitude (N): 8°31'16.00" N Longitude(E): 76°55'37.00" E The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and	Date of submission of Application	14 ^{tu} November 2017
Car Parking	Total Built up Area & No. of Floors	blocks, 1. Hospital Block (Basement+G+7 Floors): 20, 718 Sqm 2. Service Block (G+4 Floors):3160 Sqm
Height of the building from the ground level GPS Co-ordinate The height of the building will be 36.75m from Ground Level Latitude (N): 8°31'16.00" N Longitude(E): 76°55'37.00" E The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and	No of apartments	1 -
GPS Co-ordinate Latitude (N): 8°31'16.00" N Longitude(E): 76°55'37.00" E The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and		The height of the building will be 36.75m from
Brief description of the project. The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and		Latitude (N): 8°31'16.00" N
under PMSSY scheme.	Brief description of the project.	The project is proposed for Construction of New Hospital Building for Augmentation of Sree Chitra Thirunal Institute for Medical Sciences and Technology (SCTIMST), Thiruvananthapuram
Is it a new Project or expansion/modification of an existing project? Expansion	expansion/modification of an existing	Expansion
Details of the Project Cost The estimated cost for the proposed project is 230	<u> </u>	The estimated cost for the proposed project is 230

	·
If CRZ recommendation applicable? Distance from nearby habitation	crores. 1. For construction of new hospital building is Rs. 150.29 crores 2. For equipment is Rs. 79.71 crores. The funding agencies for the proposed projects will be 1. Ministry of Health & family Welfare (MoH&FW) through PMSSY for Rs. 120 crores. 2. Department of Science & Technology (DST), Govt. of India for Rs. 110 Crores. Not Applicable The proposed project is in Thiruvananthapuram city and is within the limits of Manieral Comparetion of Science of Scien
	and is within the limits of Municipal Corporation of
Distance from nearby forest if applicable	Thiruvananthapuram.
Distance from nearby forest, if applicable Distance from protected area, Wildlife	<u>-</u>
Sanctuary, National Park etc.	
	The request water had found the grant of the state of the
Distance from nearby streams/rivers/National Highway Roads and Airport Is ESA applicable? If so, distance from ESA limit	The nearest water body from the proposed project site is Akkulam Lake which is 2.5Km far from the site in western direction. The proposed hospital building is adjacent to 7m wide (average) KSEB road which connects Medical College – Kumarapuram Road at a distance of about 0.5Km. This road connects NH-47 (Ullor – Akkulam Road) in North and Poonthi road in South. Trivandrum International Airport is 3.8 Km (South) from the project site. Nearest railway station is Kochuveli RS in southwest direction about 3.4 Km and Trivandrum Central Railway station is at a distance of 4.7 Km in Southeast from the project site. Not Applicable
	I ON WATER
Details of water requirement per day in KLD Water source/sources.	The total water requirement for existing and proposed buildings will be 317 KLD. Fresh Water requirement is 211 KLD and Treated Sewage water requirement for toilet flushing and greenbelt will be 106 KLD. Kerala Water Authority(KWA) / rain Water Roof top water will be collected in rain water
Details of water requirements met from water harvesting.	collection tanks and will be utilized for domestic purposes. Provisions will be made for effective utilization of rain water in rainy days and also for ground water recharging.
What are the impacts of the proposal on the	No proposal is made for utilization of ground
ground water?	water in the proposed project.
	IANAGEMENT
Explain the facilities for Liquid waste Management	Mobile STP/ Septic tank followed by soak pit will be utilized for treatment of sewage water in construction phase. 350 KLD STP plant is proposed for treatment

	[]
	for liquid wastes in operational phase. Treated
	waste water will be reused in the project site
	itself for flushing, gardening and HVAC system.
	Excess water will be drained out as per CPCB
	discharge standards.
	Construction phase:
	Construction waste/debris will be utilized in
	the project site for leveling and strengthening of
	internal roads and remaining will be disposed in
	identified disposal sites or will be utilized for
	filling of low lying areas by consulting local
	governing bodies. The recyclable non
	biodegradable waste salvaged from the
·	debris like cement blocks, wood, iron bars,
	aluminum sections etc. would be re-used
	or sold to the vendors.
	In construction phase 120 no. of labour will be
	hired from local areas. The total solid waste
	generation is 60 Kg/day. Non biodegradable and
Solid Maste Management	packing material will be stored separately in the
Solid Waste Management	site. The biodegradable solid waste will be
	disposed through bio-bin system for microbial
	composting and domestic sewage will be treated
	in septic tank followed by soak pit or by using
	mobile STP.
	Operational phase:
	In operational phase, the total solid waste
	generation will be 634.5 Kg/day from existing
	and proposed buildings. This waste will be
	segregated according their characteristics and
	disposed to municipal Corporation garbage
	collection centers.
	Biomedical waste of quantity 158.6 Kg/day
	would be given to IMAGE(Indian Medical
	Association) for treatment as per PCB norms.
	Total E- Waste generated is 650 Kg/Year,
E Wasta Managament	The E-Waste will be stored in earmarked place
E-Waste Management	and will be sent to Authorized E-waste
	collection centers/ recyclers.
Facilities for Sewage	It is proposed to construct 350 KLD sewage
Treatment Plant	treatment plant
How much of the water requirement can be	106 KLD of recycled water will be utilized for
met from the recycling of treated waste water?	flushing, gardening and operation of HVAC
(Facilities for liquid waste treatment)	systems.
What is the incremental pollution load from	Total availability of treated water from STP will
waste water generated from the proposed	be 241 KLD after evaporation and treatment
activities?	losses. Out of which 106 KLD will be utilized
	for toilet flushing, greenbelt development and
	operation of HVAC systems. The excess water
	will be drained out as per the CPCB discharge
	standards.
How is the storm water from within the site	All along the road network and the arterial roads
managed?	of the proposed project, storm water drains
manageu:	would be provided to collect water during rains.
	would be provided to contest water during rams.

	· · · · · · · · · · · · · · · · · · ·
	They would adequately sized to prevent over flooding of the site. Vertical rain water pipes will be provided as per requirement and as per the site conditions which
	will collect the rain water through kurrahs to discharge into masonry storm water chambers with RCC covers.
	Roof top rain water will be collected in separate
	sumps and used for non flushing use which will minimize the water demand stress on Kerala
	Water Authority on fully occupancy of the project. Any over flow from the rain water sump will be connected to the storm water drain adjacent to the campus, so as to avoid flooding
YTTH A LANGUAGE	of the premises.
Will the deployment of construction labourers particularly in the peak period lead to	No labour camp is proposed for construction labour. Labour will be hired from surrounding
unsanitary conditions around the project site	localities. However, adequate no. of toilets will
(Justify with proper explanation)	be arranged for construction labors. Mobile STP/ Septic tank followed by soak pit will be arranged for treatment of domestic waste water.
What on- site facilities are provided for the	All facilities will be provided for collection of
collection, treatment & safe disposal of	effluent water and sewage water. Effluent water
sewage? (Give details of the quantities of	will be collected in separate collection tank and
wastewater generation, treatment capacities with technology & facilities for recycling and	it will be neutralized before pumped into STP. It is proposed to construct 350 KLD STP based on
disposal)	MBBR technology.
Give details of dual plumbing system if	Dual plumbing system will be arranged in the
treated waste is used for flushing of toilets or any other use.	proposed project for reuse of treated waste water for domestic, gardening and operation of HVAC
TRAFFIC MANAGEMENT	etc.
Sufficiency of Parking Space (Explain)	Multi level car parking is proposed for 200 cars
Width of access road	7 meters
ENERGY CONSERVATION	
Details of power requirement and source of supply, backup source etc. What is the energy consumption assumed per square foot of built-	Power requirement for the proposed project will be 2500 KVA. Power will be met from Kerala State Electricity Board (KSEB).
up area? How have you tried to minimize	For hot water requirement, it is proposed to
energy consumption?	install solar water heaters. Solar based street
	lighting system on internal roads will be planned.
What type of, and capacity of power back-up to you plan to provide?	For the provision of backup power supply during the power failure there is provision of 2
to you plan to provide:	no. of DG sets of 1250 KVA capacity 1x 1250
	KVA as standby. 2 X 500 KVA and 1 X 320
	KVA DG sets were already installed for existing
	building.
I .	Two numbers of 200 KVA UPS also will be
·	installed to supply essential load of medical
What are the characteristics of the glass you	
What are the characteristics of the glass you plan to use? Provide specifications of its characteristics related to both short wave and	installed to supply essential load of medical equipments, lights etc.

long wave radiation?	
Tong wave fadiation:	All the relevant features are incorporated like
What passive solar architectural features are	the orientation of the building, shading effect
being used in the building? Illustrate the	etc. Double glazing windows, carefully designed
applications made in the proposed project	shading devices will be installed. The building is
	designed to achieve 4 star rating as per GRIHA.
Does the layout of streets & buildings	Due consideration has been taken for maximum
maximize the potential for solar energy	use of the solar energy while preparation of
devices? Have you considered the use of	layout plan. The project proponent shall make
street lighting, emergency lighting and solar hot water systems for use in the building	provision for solar panel system (hot water purpose) in building and solar energy devices
complex? Substantiate with details	will be used for street lighting, emergency
Total Print Woods and William Works and Works an	lighting in the proposed project.
Is the shading effectively used to reduce	All the relevant features are incorporated like
cooling/heating loads? What principles have	the orientation of the building, shading effect
been used to maximize the shading of Walls	etc. The building is designed to achieve 4 star
on the East and the West and the Roof? How	rating as per GRIHA.
much energy saving has been effected?	
Do the structure use energy-efficient space conditioning, lighting and mechanical	Suitable energy optimization will be adopted during the calculation of energy load of the
conditioning, lighting and mechanical systems? Provide technical details. Provide	proposed project. The space heating load will be
details of transformers and motor efficiencies,	minimized using passive solar structure and
lighting intensity and air-conditioning load	suitable buildings envelop material. Uses of
assumptions? Are you using CFC and HCFC	incandescent lamp and halogen lamps have been
free chillers? Provide specifications.	avoided and energy efficient LED lamps will be
	used for all common area. The diesel generator
	sets shall be automatically controlled to
	optimize their usage based on the actual load requirements at any time. Variable frequency
	drive systems would be adopted for the lifts etc.
	to maximize the energy saving.
	The proposed project site is devoid of any
	vegetation and plot area of the site is only 5,500
What are the likely effects of the building	sqm. Because of this proposed project there will
activity in altering the micro-climates? Provide	be negligible impact on micro climate of project
a self assessment on the likely impacts of the	site. However, paved areas will be covered with
proposed construction on creation of heat	canopy of tree shade, open spaces will be covered with grass turf and with garden shrubs
island & inversion effects?	so that heat absorption by paving material will
	be minimized. This will mitigate the heat island
	effect to a large extent.
What are the thermal characteristics of the	The building materials will be selected with
building envelope? (a) Roof (b) external walls;	characteristics that limit heat ingress into the
and (c) fenestration? Give details of the	inside of the building will be minimized.
materials used.	U value R value
	(W/m2-9C) (m2-9C/W) Roof U-0.409 R-2.1
	Fenestration 3.177 0.25
What is the rate of air non-conventional	The uses of non-conventional source of energy
energy technologies are utilized in the overall	in the proposed construction project are as
energy consumption? Provide details of the	follows: Solar Water Heater: The proposed project
renewable energy technologies used.	bolal water freater: The proposed project

would install solar panels for hot requirements in the project and hence the dependency on electricity for hot water generation can be minimized. Solar Street Light: It is also suggested to use solar cell powered street lights within the proposed project site for conservation of electricity. Use of LED Lamps: The project proponent would use LED Lamps which consumes less electricity. **Lighting:** The orientation of the building of the proposed project are designed in such a way that natural ventilation and natural light in the non-air conditioned buildings so that the use of lights during day time can be minimized. Details of renewable energy (non -The uses of non-conventional source of energy conventional) used. in the proposed construction project are as follows: Solar Water Heater: The proposed project would install solar panels for hot water requirements in the project and hence the dependency on electricity for hot water generation can be minimized. Solar Street Light: It is also suggested to use solar cell powered street lights within the proposed project site for conservation of electricity. Use of LED Lamps: The project proponent would use LED Lamps which consumes less electricity. **Lighting:** The orientation of the building of the proposed project are designed in such a way that natural ventilation and natural light in the non-air conditioned buildings so that the use of lights during day time can be minimized. IMPACT ON AIR ENVIRONMENT What During construction phase, dust generation will the mitigation are measures generation of dust, smoke, odors, fumes or be controlled by regular water sprinkling for hazardous gases dust suppression. Barricades will be installed all around the construction site to control the exposure of fugitive dust to surrounding areas. Trucks will be covered with tarpaulin covers. DG sets will be maintained as per CPCB standards and vented out through appropriate stack height. Details of internal traffic management of the The conceptual plan shows the internal traffic site. management with entry and exit to the proposed project site. All internal roads with proper width, pedestrian path ways etc will be provided. Further, provisions of ramps are proposed for the easy access to the building for each floor. The area allotted for internal roads/ pedestrian pathways/ footpaths in the site is 2000 Sqm.

Details of noise from traffic, machines and vibrator and mitigation measures Air quality monitoring in detail	No significant impact of noise is anticipated within and outside of the project site due to provision of wide roads for smooth flow of traffic and greenbelt. Noise, due to the traffic, within site, will result in a marginal increase in the noise levels because noise control measures is provided in vehicles & DG sets, which cause slight increase in noise level. Regular air quality Monitoring will be carried out as per Kerala Pollution Control Board
Will the proposal create shortage of parking space for vehicles? Furnish details of the present level of transport infrastructure and	norms. The proposed project would provide vehicle parking facilities within the project premises. It is proposed to install multi level parking to
measures proposed for improvement including the traffic management at the entry & exit to the project site.	facilitate parking area for 200 cars and two wheeler parking will be provided in the existing campus
	At construction stage, parking facility will be provided at back side of the Achyutamenon Block. The parking plan for this project would follow KPBR/KMBR guidelines.
Provide details of the movement patterns with internal roads, bicycles tracks, Pedestrian pathways, footpaths etc., with areas under each category	The conceptual plan shows the internal traffic management with entry and exit to the proposed project site. All internal roads with proper width, pedestrian path ways etc will be provided. Further, provisions of ramps are proposed for the easy access to the building for each floor. The area allotted for internal roads/ pedestrian pathways/ footpaths in the site is 2000 Sqm.
Will there be significant increase in traffic noise & vibrations? Give details of the sources and the measures proposed for mitigation of the above.	No significant impact of noise is anticipated within and outside of the project site due to provision of wide roads for smooth flow of traffic and greenbelt. Noise, due to the traffic, within site, will result in only a marginal increase in the noise levels because noise control measures is provided in vehicles & DG sets, which cause slight increase in noise level.
What will be impact of DG sets & other equipments on noise levels & vibration in & ambient air quality around the project site? Provide details	At present vehicular movement and operation of DG sets are the major sources of noise pollution. DG set is not operational continuously and they will be enclosed with suitable enclosures, hence minimal impact is anticipated. It is envisaged that the movement of the motor vehicles is restricted to designated carriageways only.
IMPACT ON BIODIVERSITY AND F	ECO RESTORATION PROGRAMMES
Will the project involve extensive clearing or modification of vegetation (Provide details)	No. There are no major trees available in the site.
What are the measures proposed to minimize the likely impact on vegetation (details of proposal for tree plantation/landscaping)	During the development of the green belt within the project area, it has to be emphasized that those native plant species should be planted which are having good ornamental values and fast growing with excellent canopy cover.
Is there any displacement of fauna - both	No ·

terrestrial and aquatic? - If so what are the mitigation measures? Presence of any endangered species or red listed category (in detail) SOCIO- ECONOMIC ASPECTS Will the proposal result in any change to the The proposed project is an expansion of the demographic structure of local population? existing hospital facility. After the proposed Provide the details. expansion, during operation phase on full occupancy of the project, additionally 923 employees will be deputed and the more floating population is expected and hence there will be influx of people to the project area and surrounding. Give details of the existing social Infrastructure facilities such as, transportation, infrastructure around the proposed project water supply & sanitation, communication, educational institutes, hospital, markets, banks, cultural amenities etc. already exist in area near the project site. Will the project cause adverse effects on local No adverse effects are anticipated. The project communities, disturbances to sacred sites or has generated employment opportunity and improves health facilities in the region as well in other cultural values? What are the safeguards proposed? country. S.No. Purpose in Sqm Hospital 2328 1. Proposed Building 2. Services Building 377 3. Multi Level Parking 500 Out of the total plot area % of spaces provided 4. Water Treatment Plant 94 i)Recreational facility 5. Oxygen Plant 50 ii)Parking iii)Open Spaces 6. Internal Roads 2000 Open Area 151 Total 5500 Recreational facility is already available in adjacent building. **BUILDING MATERIALS** May involve the use of building materials with The proposed hospital building will be designed high-embodied energy. Are the construction to meet the four stars rating as per GRIHA. materials produced with energy efficient Low energy embodied materials will be process? (Give details of energy conservation given preference. measures in the selection of building materials • Energy efficient construction materials such and their energy efficiency) as Gypsum Plaster Concrete, Sand, Aggregate, Fly Ash Cement, will be used to achieve the desired primary energy efficiency. Ready Mix concrete will be used for construction of RCC structures, M-sand will be used as an alternative to river sand and the building blocks will be solid cement blocks that are energy efficient and work efficient compared to baked bricks.

Ensuring that the building materials and products have low energy embodied energy. • Minimizing the transport of temporary structures, scaffolding, formwork, consumables and building product to the construction site. • Minimizing overall waste and the transport of waste from site. • Use of energy efficient lighting. • Ensuring idle construction equipment is throttled down or switched off All the items to be used in the project are as per the National Building Code-2005. All vehicles which bring construction material Transport and handling of materials during construction may result in pollution, noise & to the site would possess Pollution Under public nuisance. What measures are taken to Control Certificates (PUC). All vehicles would be of close body to avoid spread of dust from minimize the impacts? the loose materials, and vehicles which bring sand, stone dust, etc. would ensure that the above mentioned material are properly wetted during transportation to avoid dust generation. Pucca Road to be made in the construction site for the vehicle movement so that the dust generation due to the vehicular movement within the project site can be minimized. Stacking of construction material shall be confined to the project site only. All the D.G. Sets would have attached with acoustic enclosure for the sound pollution control and all sound generating construction activity to be minimized. Further barricading of the site with GI sheets of 10 ft height in the side abutting the public road during construction The plastic (non-biodegradable solid waste) will Are recycled materials used in roads and be used along with coal tar during the structures? State the extent of savings construction of internal roads. This will increase achieved? the life of roads. Give details of the methods of collection, The municipal solid waste generated after full occupancy of the hospital is expected to be segregation & disposal of the garbage 634.5 kg/day from existing and proposed generated during the operation phases of the buildings. About 158.6 kg/day bio-medical project. waste will be generated and it will be given to IMAGE who will arrange its disposal as per PCB norms. Hazardous wastes generated in the project site will be used oil, cotton waste and used batteries from DG Sets. These wastes will be disposed to authorized approved recyclers. The used oil will be stored in isolated covered HDPE drums. Used batteries will return back to the dealer to purchase new batteries on buy back basis. The quantities of hazardous waste will be; Used Oils-700 LPA, o Used Batteries - 4

	no's/year (Average), Cotton Waste – 750 Kg/ Year • Bio-medical waste generated in operational period will be given to IMAGE who will arrange its disposal as per PCB norms. • incinerated by using incinerator of
	capacity 100kg/hour within the project site area. The incinerator ash will be stored in lined sump and disposed off to authorized recyclers/Fly ash brick manufacturers etc. • About 20 kg/ day of sludge will be generated from STP. The sludge will be used as manure for greenbelt development • E-Waste: Discarded computer parts,
	electronic and electrical items will be stored in an earmarked area. E-waste will be generated after 4-5 years latency period. E-waste will be disposed as per E Waste (Management & Handling) Rules. • Radioactive Waste: No radioactive waste is generated.
RISK MAI	NAGEMENT
Are there sufficient measures proposed for risk hazards in case of emergency such as accident at the site during construction & post construction phase.	Yes. Sufficient measures are proposed for risk hazards in case of emergencies during construction and operational phases.
Storage of explosives/hazardous substance in detail	Used Oil generated from the D.G. sets will be stored in HDPE drums on separate and isolated concrete floor and it will be sold to CPCB approved recyclers. HSD for DG sets will be sourced from local traders. Small quantities of HSD will be stored at the site to use during power failures.
What precautions & safety measures are proposed against fire hazards? Furnish details of emergency plans	Smoke detectors and Fire Fighting systems will be installed in the building and at all services areas. Emergency fire fighting plan and evacuation routes will be displayed at appropriate places on each floor of building.
Litigation/court cases if any	No
	HETICS
Will the proposed constructions in any way result in the obstruction of a view, scenic amenity or landscapes? Are these considerations taken into account by the proponents?	There is no scenic beauty near the project site. Therefore, the proposed project in no way work as an obstruction of view.
Will there be any adverse impacts from new constructions on the existing structures? What are considerations taken into account?	There will be no adverse impacts due to the development of the proposed project.
Whether there are any local considerations of urban form & urban design influencing the design criteria? They may be explicitly spelt out.	The proposed project would be constructed in conformity with the Kerala Municipal Building Rules (KMBR). Project design will be based on 4 star rating as per GRIHA rating system. As per seismic classification, the project site

	falls in Zone-III. Structural design aspects as per the seismic codes – IS 1893 (2002), IS 13920 (1993) and IS 456 (2000) as applicable would be
	incorporated in the project.
Are there any anthropological or	No anthropological or archaeological sites or
archaeological sites or artefacts nearby? State	artifacts are found near the site area.
if any other significant features in the vicinity	
of the proposed site have been considered	
Details of CSR activity and the amount set apart per year	It has striven to offer services at very affordable costs, including subsidized costs for those in the lower income groups and completely free treatment to the destitute. It has set a unique model by offering the same high standard of care as well as uniform facilities to patients from all walks of life, thus holding the principle of equity high. Based on the socio economic status of the patients, in the past year, out of total in & out patients, 1% of the patients were provided with 100% free treatment and 40 % of the
	patients were offered concessional treatment
	ranging from 10% to 60%.
Details of NABET approved EIA Consultant	EIA Consultant
engaged-Their name, address and accreditation	M/s. VISON LABS
details	# 16-11-23/37/A, Flat No. 205, 2nd Floor, Opp.
	RTA Office, Moosarambagh, Malakpet,
	Hyderabad - 500 036
	Phone: 040-24544320/65792001
	FAX: 040-24544320
	E-mail: info@visonlabs.com,
	vison.labs@gmail.com
·	URL: www.visonlabs.com
	NABET SI.No. 144, DATED 16.10.2017
Details of Authorized Signatory and address	Dr. Asha Kishore, MD, DM, Director,
for correspondence	Sree Chitra Thirunal Institute for Medical
	Sciences and Technology, Medical College
	campus,Medical College PO
	Thiruvananthapuram -695 011
	Thiruvananthapuram,
	D CONCLUSION
Overall justification for implementation of the	It is evident that the project aims at maximizing
project.	the project benefits to the people around the site,
	the region and the state in general. Appropriate
	measures would be taken to mitigate negative
	impacts.
	This project will be very beneficial to the people
	of Kerala and country.
	There are no adverse impacts the proposed
Explanation of how adverse impacts have been	project. However environmental management
mitigated.	plan will be effectively implemented in
	operational phase to minimize the impacts as
1	extent as possible

2. The proposal was placed in the 83rd meeting of SEAC held on 20th & 21st December 2017. The Committee decided to defer the item for field inspection. The Committee also directed the proponent to submit the additional documents/ clarifications.

Accordingly inspection was conducted by a sub committee consisting of Sri S Ajayakumar, Dr. Oommen V. Oommen, Sri John Mathai and Sri Sreekumaran Nair on 13.01.2018. The report states

The proposal is for an expansion of the existing Sree Chithra Thirunal Institute of Medical Sciences and Technology with a new 170 bed Hospital building, Service block and multilevel car parking facility proposed on the south –eastern side adjacent to the Achutha Menon Centre. Proposed total built up area is 28,478 sq.m.in 5500 sq.m plot. As per Form 1 application, SCTIMS has 21,585 sq.m of existing built up area for hospital which has been completed prior to 1986. An additional 7,511 sq.m built up area is used for educational purposes. Based on the overall evaluation of the site and on the points raised in the meeting, following aspects need consideration

- a) The layout plan of the entire Institute drawn to a larger scale indicating the foot print of the existing buildings and those proposed is to be submitted. The projection provided to the ground floor of the building on the northern side of Nurses hostel can be avoided. The high level connecting corridor between the old block and proposed building should also be indicated.
- b) It is mentioned in the proposal that the Nurses hostel will be demolished, but at the time of site inspection it is informed that it will be retained. This need clarification.
- c) The proposed building is planned in the existing parking space. Alternate parking space to be made available during the construction stage.
- d) The fugitive dust barricade provided presently is of a nylon shade. Considering the presence of hospitals in the vicinity demanding a dust proof zone, adequate measures to be adopted to prevent movement of dust from the site. The height of the barricade must also be enhanced appropriately.
- e) The entry to the building is from the main drive way of 7 m width located between the old block and proposed building. This is a common road used by the OP facility of Medical college and the Dental College necessitating widening at the entry from the main road and stream lining the traffic. Considering a higher level of traffic and movement of pedestrians, the road need to be widened to a minimum width of 10m all along including foot path of minimum 1.5 m on either sideand prohibiting any kind of parking in this road. Necessary land for widening is to be surrendered from the proponent. The entry to the building and to MLCP needs suitable modification with adequate splay necessary for ambulances and bus. The connecting road to the service block should be provided with adequate slope to permit the movement of fire fighting vehicles.

- f) The present proposal for car parking of 200 cars is inadequate for this facility. The topography permits an additional floor in the basement that can be used as dedicated parking for the staff which must be explored and reported. In addition, the MLCP facility should be planned with at least three additional floors to accommodate the increasing requirements in future.
- g) The storm water from the campus appears to be let out through the narrow drains. The storm water lines have to be redesigned so as to dispose the water safely. This must form part of the plan.
- h) The rainwater harvesting facility should have a minimum capacity of 1500 KL. The efforts to provide separate treatment facility for the grey and dark water are appreciated.
- i) Considering the sloping nature of the terrain and the occurrence of laterite clay substrate, excavation should be done with adequate safety to the cut slope. Slumping and failure can affect the stability of existing structures.
- j) The quantity of earth to be taken out of the site must be reported and if it is to be taken out it should be given for use of Govt. projects like NH
- k) Use of solar power should be maximised and the quantity that is planned to be generated daily should be reported.
- l) The material recovery facility (MRF) should be clearly demarcated and should have a capacity of at least a week's storage. Food waste and the like should be used for generation of biogas.
- m) A dedicated open space should be designated and left as assembly point
- n) The proponent shall submit a revised site plan showing the changes.
- 3. The proposal was placed in the 84th SEAC meeting held on 22 & 23rd January 2018 and directed the proponent to submit the documents/clarifications as suggested by the inspection team.

The proponent has been submitted the documents sought by SEAC. A meeting was conducted on 03.02.2018 by a Subcommittee of SEAC consisting of Sri S Ajayakumar & Sri John Mathai. The Construction Engineer & Executive Engineer of Sree Chitra Thirunal Institute for Medical Sciences & Technology attended the meeting.

The proponent submitted the documents sought by the Sub Committee.

4. The proposal was placed in the 85th meeting of SEAC held on 12th February 2018. The Committee appraised the proposal based on Form 1, Form I A, Conceptual Plan, field inspection report of the Sub Committee and all other documents submitted with

the proposal. The Sub Committee which inspected the site on 13.01.2018 made few suggestions and sought clarifications on certain points. The representatives of the proponent appeared before the Subcommittee with the clarifications and details on 03.02.2018. After examining the details, the Sub Committee found that the FAR is within the limits. The proponent also submitted satisfactory explanation regarding the demolition of Nurses Hostel. The solar power proposed to be generated and the earth to be taken out are quantified. The proponent also expressed the difficulty in enhancing the capacity of the multilevel car parking, which was accepted.

After deliberations, the Committee decided to recommend EC subject to the general conditions in addition to the following specific conditions:

- a) The entry to the building is from the main drive way of 7 m width located between the old block and proposed building. This is a common road used by the OP facility of Medical college and the Dental College necessitating widening at the entry from the main road and stream lining the traffic. Considering a higher level of traffic and movement of pedestrians, the road need to be widened to a minimum width of 10m all along including foot path of minimum 1.5 m on either side and prohibiting any kind of parking in this road. Necessary land for widening is to be surrendered from the proponent.
- b) The present proposal for car parking of 200 cars is inadequate for this facility. In addition, a MLCP facility should be planned with at least three additional floors to accommodate the increasing requirements in future.
- c) The storm water from the campus appears to be let out through the narrow drains. The storm water lines have to be redesigned so as to dispose the water safely. This must form part of the plan.
- d) The rainwater harvesting facility should have a minimum capacity of 1500 KL.
- e) Considering the sloping nature of the terrain and the occurrence of laterite clay substrate, excavation should be done with adequate safety to the cut slope. Slumping and failure can affect the stability of existing structures.
- f) The material recovery facility (MRF) should be clearly demarcated and should have a capacity of at least a week's storage. Food waste and the like should be used for generation of biogas.
- g) A dedicated open space should be designated and left as assembly point
- 5. The proponent has submitted a Letter No.CIVIL/SCTIMST/NHB dt.06.03.2018 requesting that specific mention on the quantity of earth to be removed from the site may be incorporated in the EC to be issued from SEIAA.
- 6. The proposal was placed in the 81st meeting of SEIAA held on 8th March 2018. Authority accepted the recommendation of SEAC and decided to issue EC subject to general conditions in addition to the above specific condition as suggested by SEAC. Dependable source of water from Kerala Water Authority is to be ensured. Sanction is also given for excavating upto 21000 m³ of earth from the project site. A notarised affidavit for the commitment of CSR activities and also agreeing all the above specific and general conditions should be submitted before the issuance of EC. The proponent has submitted the affidavit vide ref 7th cited stating that all the specific and

general conditions shall be strictly implemented.

Environmental Clearance as per the EIA notification 2006 is hereby accorded for the Augmentation of proposed Hospital Building of Sree Chitra Thirunal Institute for Science Technology Medical College and (SCTIMST), in Survey No. 44 & 42/1 Part Block No.6 Cheruvackal Village, Thiruvananthapuram Thiruvananthapuram by the Director Dr.Asha Kishor, MD,DM under PMSSY scheme of proposed built-up area 28,478 sqm subject to the conditions mentioned in para 4 & 6 above and the usual general conditions for projects other than mining appended hereto and the following green conditions should be strictly adhered to. Sanction is also accorded for excavation of 21,000m³ of earth from the project site.

Green Guidelines

- 1. Adequate rain water harvesting facilities shall be arranged for.
- 2. Technology and capacity of the STP to be indicated with discharge point (if any) of the treated effluent.
- 3. Effluent water not conforming to specifications shall not be let out to water bodies.
- 4. Maximum reuse of grey water for toilet flushing and gardening and construction work shall be ensured.
- 5. Dual plumbing for flushing shall be done.
- 6. Provisions for disposal of e-wastes, solid wastes, non-biodegradables and separate parking facility for the buildings shall be provided.
- 7. Generation of solar energy to be mandatory for own use and/or to be provided to the grid.
- 8. There shall be no compromise on safety conditions and facilities to be provided by the project proponent, which shall be ensured for occupation, regularization or consent to operate.
- 8. The clearance will be subject to all the environmental impact mitigation and management measures envisaged by the project proponent in the documents submitted to SEIAA, and the mitigation measures specified. The assurances in form 1A of the application (Appendix 1I) and clarifications given by the proponent will be deemed to be part of these proceedings as if incorporated herein. Also the general conditions for projects other than mining appended hereto and the following green guidelines will be applicable and have to be strictly adhered to.
- 9. Validity of the Environmental Clearance will be seven years from the date of issuance the subject to earlier review in the event of noncompliance or violation of any of the conditions stipulated herein.
- 10. Compliance of the conditions herein will be monitored by the State Environment Impact Assessment Authority or its agencies and also by the Regional Office of the Ministry of Environment and Forests, Govt. of India, Bangalore.
 - i) Necessary assistance for entry and inspection by the concerned officials and staff should be provided by the project proponents.

- ii) Instances of violation if any shall be reported to the District Collector, Thiruvananthapuram to take legal action under the Environment (Protection) Act 1986.
- iii) The given address for correspondence with the authorized signatory of the project is, Dr.Asha Kishore,MD,DM, Director, Sree Chitra Institute for Medical Science and Technology, Medical College Campus, Medical College.P.O., Thiruvananthapuram 695 011.

Sd/-P H.Kurian I.A.S Member Secretary (SEIAA),

To

Dr. Asha Kishore, MD, DM, Director,
Sree Chitra Institute for Medical Science and Technology,
Medical College Campus,
Medical College. P.O.,
Thiruvananthapuram – 695 011.

Copy to:

- MoEF Regional Office, Southern Zone, Kendriya Sadan, 4th Floor, E&F Wing, II Block, Koramangala, Bangalore-560034
- 2. Additional chief Secretary to Government, Environment Department,
- 4. The District Collector, Thiruvananthapuram
- 3. The District Town Planner, Thiruvananthapuram
- 5 Tahsildar, Thiruvananthapuram Taluk
- Member Secretary, Kerala State Pollution Control Board,
 Pattom, Thiruvananthapuram
- 7. Chairman, SEIAA
- 8 The Secretary, Thiruvananthapuram Corporation
- Website
- 10. Stock File
- 11. O/c

Forwarded /By Order

Administrator(SEIAA



GENERAL CONDITIONS (for projects other than mining)

- (i) Rain Water Harvesting capacity should be installed as per the prevailing provisions of KMBR / KPBR, unless otherwise specified elsewhere.
- (ii) Environment Monitoring Cell as agreed under the affidavit filed by the proponent should be formed and made functional.
- (iii) Suitable avenue trees should be planted along either side of the tarred road and open parking areas, if any, inclusive of approach road and internal roads.
- (iv) The project shall incorporate devices for solar energy generation and utilization to the maximum possible extent with the possibility of contributing the same to the national grid in future.
- (v) Safety measures should be implemented as per the Fire and Safety Regulations.
- (vi) STP should be installed and made functional as per KSPCB guidelines including that for solid waste management.
- (vii) The conditions specified in the Companies Act, 2013 should be observed for Corporate Social Responsibility.
- (viii) The proponent should plant trees at least 5 times of the loss that has been occurred while clearing the land for the project.
 - (ix) Consent from Kerala State Pollution Control Board under Water and Air Act(s) should be obtained before initiating activity.
 - (x) All other statutory clearances should be obtained, as applicable, by project proponents from the respective competent authorities including that for blasting and storage of explosives.
- (xi) In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Authority.
- (xii) The Authority reserves the right to add additional safeguard measures subsequently, if found necessary, and to take action including revoking of the environment clearance under the provisions of the Environment (Protection) Act, 1986, to ensure effective implementation of the suggested safeguard measures in a time bound and satisfactory manner.
- (xiii) The stipulations by Statutory Authorities under different Acts and Notifications should be complied with, including the provisions of Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and control of Pollution) act 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006.
- (xiv) The environmental safeguards contained in the EIA Report should be implemented in letter and spirit.
- (xv) Provision should be made for supply of kerosene or cooking gas and pressure cooker to the labourers during construction phase.
- (xvi) Officials from the Regional of MOEF, Banglore who would be monitoring the implementation of environmental safeguards should be given full co-operation, facilities and documents/data by the project proponents during their inspection. A complete set of all the documents submitted to MoEF should be forwarded to the CCF, Regional Office of MOEF, Bangalore.
- (xvii) These stipulations would be enforces among others under the provisions of Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control Pollution) at 1981, the Environment (Protection) Act, 1986, the Public Liability (Insurance) Act, 1991 and EIA Notification, 2006.

(xviii) Environmental Clearance is subject to final order of the Hon'ble Supreme Court of India in the matter of Goa Foundation Vs. Union of India in Writ Petition (Civil) No.460 of 2004 as may be applicable to this project.

(xix) Any appeal against this Environmental Clearance shall lie with the National Environment Appellate Authority, if preferred, within a period of 30 days as prescribed under section

11 of the National Environment Appellate Act, 1997.

The project proponent should advertise in at least two local newspapers widely circulated in the region, one of which (both the advertisement and the newspaper) shall be in the vernacular language informing that the project has been accorded Environmental Clearance and copies of clearance letters are available with the Department of Environment and Climate Change, Govt. of Kerala and may also be seen on the website of the Authority at www.seiaakerala.org. The advertisement should be made within 10 days from the date of receipt of the Clearance letter and a copy of the same signed in all pages should be forwarded to the office of this Authority as confirmation.

(xxi) A copy of the clearance letter shall be sent by the proponent to concerned GramaPanchayat/ District Panchayat/ Municipality/Corporation/Urban Local Body and also to the Local NGO, if any, from whom suggestions / representations, if any, were received while processing the proposal. The Environmental Clearance shall also be put

on the website of the company by the proponent.

The proponent shall submit half yearly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) and upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the respective Regional Office of MoEF, Govt. of India and also to the Directorate of Environment and Climate Change, Govt. of Kerala

(xxiii) The details of Environmental Clearance should be prominently displayed in a metallic board of 3 ft x 3 ft with green background and yellow letters of Times New Roman font of size of not less than 40.

(xxiv) The proponent should provide notarized affidavit (indicating the number and date of Environmental Clearance proceedings) that all the conditions stipulated in the EC shall be scrupulously followed.

SPECIFIC CONDITIONS

I.Construction Phase

- i. "Consent for Establishment" shall be obtained from Kerala State Pollution Control Board under Air and Water Act and a copy shall be submitted to the Ministry before start of any construction work at the site.
- ii. All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.
- iii. A First Aid Room will be provided in the project both during construction and operation of the project.
- iv. Adequate drinking water and sanitary facilities should be provided for construction workers at the site, Provision should be made for mobile toilets. The safe disposal of wastewater and solid wastes generated during the construction phase should be ensured.
- v. All the topsoil excavated during construction activities should be stored for use in horticulture/landscape development within the project site.

- vi. Disposal of muck during construction phase should not create any adverse effect on the neighbouring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- vii. Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- viii. Construction spoils, including bituminous material and other hazardous materials, must not be allowed to contaminate watercourses and the dump sites for such material must be secured so that they should not leach into the ground water.
- ix. Any hazardous waste generated during construction phase, should be disposed off as per applicable rules and norms with necessary approval of the Kerala State Pollution Control Board.
- x. The diesel generator sets to be during construction phase should be low sulphur diesel type and should conform to Environment (Protection) Rules prescribed for air and noise emission standards.
- xi. The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from Chief Controller of Explosives shall be taken.
- xii. Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to the applicable air and noise emission standards and should be operated only during non-peak hours.
- xiii. Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/KSPCB.
- xiv. Fly ash should be used as building material in construction as per the provisions of Fly Ash Notification of September, 1999 and amended as on 27th August 2003. (The above condition is applicable Power Stations).
- xv. Ready mixed concrete must be used in building construction.
- xvi. Storm water control and its resuse per CGWB and BIS standards for various applications.
- xvii. Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
- xviii. Permission to draw ground shall be obtained from the Computer Authority prior to construction/operation of the project.
- xix. Separation of grey and black water should be done by the use of dual plumbing line for separation of grey and black water.
- xx. Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- xxi. Use of glass may be reduced by upto 40% to reduce the electricity consumption and load on airconditioning. If necessary, use high quality double glass with special reflective coating in windows.
- xxii. Roof should meet prespective requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfil requirement.
- xxiii. Opaque wall should meet perspective requirement as per energy Conservation Building Code which is proposed to be mandatory for all airconditioned spaces while it is aspirational for non-airconditioned spaces by use of appropriate thermal insulation material to fulfil requirement.

- xxiv. The approval of the competent authority shall be obtained for structural safety of the buildings due to earthquake, adequacy of fire fighting equipments, etc. as per National, Building Code including protection measures from lightening etc.
- xxv. Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.
- under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the protect proponent if it was found that construction of the project has been started without obtaining environmental clearance.

II. Operation Phase

- i. The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the Ministry before the project is commissioned for operation. Treated affluent emanating from STP shall be recycled / reused to the maximum extent possible. Treatment of 100% grey water by decentralised treatment should be done. Discharge of unused treated affluent shall conform to the norms and standards of the Kerala State Pollution Control Board. Necessary measures should be made to mitigate the odour problem from STP.
- ii. The solid waste generated should be properly collected and segregated. Wet garbage should be composted and dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material.
- iii. Diesel power generating sets proposed as source of back up power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel. The location of the DG sets may be decided with in consultation with Kerala State pollution Control Board.
- iv. Noise should be controlled to ensure that it does not exceed the prescribed standards. During night time the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.
- v. The green belt of the adequate width and density preferably with local species along the periphery of the plot shall be raised so as to provide protection against particulates and noise.
- vi. Weep holes in the compound walls shall be provided to ensure natural drainage of rain water in the catchment area during the monsoon period.
- vii. Rain water harvesting for roof run-off and surface run-off, as plan submitted should be implemented. Before recharging the surface run off, pre-treatment must be done to remove suspended matter, oil and grease. The borewell for rainwater recharging should be kept at least 5 mts.above the highest ground water table.
- viii. The ground water level and its quality should be monitored regularly in consultation with Central Ground Water Authority.
- ix. Traffic congestion near the entry and exit points from the roads adjoining the purposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- x. A Report on the energy conservation measures confirming to energy conservation norms finalise by Bureau of Energy Efficiency should be prepared incorporating details about building materials & technology, R & U Factors etc and submit to the Ministry in three months time.

- xi. Energy conservation measures like installation of CFLs/TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Use CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible.
- xii. Adequate measures should be taken to prevent odour problem from solid waste processing plant and STP.
- xiii. The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation.

III Post Operational Phase

Environmental Monitoring Committee with defined functions and responsibility should foresee post operational environmental problems e.g. development of slums near the site, increase in traffic congestion, power failure, increase in noise level, natural calamities, and increase in suspended particulate matter etc. solve the problem immediately with mitigation measures

For Member Secretary, SEIAA